

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-099-20621-00-00
Spot: NENENW Sec/Twnshp/Rge: 21-34S-20E
5097 feet from S Section Line, 3037 feet from E Section Line
Lease Name: LINK Well #: 5
County: LABETTE Total Vertical Depth: 423 feet

Operator License No.: 9386
Op Name: GUS JONES CABLE TOOL SERVICE, LL
Address: 149 RD 25
ELK CITY, KS 67344

Well Type: ST UIC Docket No: _____ Date/Time to Plug: 05/19/2009 8:00 AM
Plug Co. License No.: 9386 Plug Co. Name: GUS JONES CABLE TOOL SERVICE, LLC
Proposal Rcvd. from: GUS JONES Company: _____ Phone: (620) 332-7637

Proposed Plugging Method: 5 1/2 INCH CASING CEMENTED WITH HIGH TEMPERATURE LUMINITE CEMENT WITH 40 PER CENT SILICA FLOUR. 1 1/2 INCH TUBING WELDED TO OUTSIDE (?) OF CASING FOR THERMOCOUPLE. PERFORATED FROM 342 TO 366 FT WITH 6 SHOTS PER FOOT. FRACTURED WITH 3000 GALLONS PAD, 3000 GALLONS FRAC FLUID WITH 1 LB./GAL 20/40 MESH SAND, 2000 GALLONS FLUSH

Plugging Proposal Received By: RUSSELL HINE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2009 1:30 PM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Ran 3/4" in thermocouple and plugged with 4 sacks. Hooked to 5-1/2" and created a rate of flow and pumped 50 sacks of 60/40 pozmix and shut in at 500psi

Perfs:

RECEIVED
KCC DIST # 3
JUL 15 2015
CHANUTE, KS
RH

Remarks: CORRECTED FOOTAGES/GPS 7/15/2015

Plugged through: CSG

CKM

District: 03

Signed

Russell Hine

(TECHNICIAN)

KCC WICHITA

JUL 21 2015

RECEIVED