

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-109-21416-00-00  
Spot: SWNWNESE Sec/Twnshp/Rge: 6-15S-32W  
2300 feet from S Section Line, 1030 feet from E Section Line  
Lease Name: FAIRLEIGH L Well #: 2  
County: LOGAN Total Vertical Depth: 4494 feet

Operator License No.: 34639  
Op Name: BLACK TEA OIL, LLC  
Address: 1014 E. 29TH ST.  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	265		225 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/23/2015 12:00 AM  
Plug Co. License No.: 33549 Plug Co. Name: LANDMARK DRILLING, LLC  
Proposal Rcvd. from: MAGGIE Company: LANDMARK DRILLING, LLC Phone: (620) 935-2036

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE  
Date/Time Plugging Completed: 06/23/2015 4:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st plug @2180 w/50 sx  
2nd plug @1038 w/100 sx  
3rd plug @315 w/50 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: GLOBAL

Plugged through: DP

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUN 30 2015

JUL 10 2015

CONSERVATION DIVISION  
WICHITA, KS