

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-20987-00-00
Spot: SWNENE Sec/Twnshp/Rge: 14-21S-7W
4622 feet from S Section Line, 770 feet from E Section Line
Lease Name: BELL FLOYD D Well #: 1-14
County: RICE Total Vertical Depth: 3488 feet

Operator License No.: 5610 •
Op Name: BRUCE OIL COMPANY, L.L.C.
Address: 1704 LIMESTONE RD
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3487	640	150 SX
SURF	8.625	209		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/01/2015 10:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE INC Phone: (620) 628-4723

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 07/01/2015 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, ENCOUNTERED BLOCKAGE AT AROUND 800'. BRING WORKING STRING OF TUBING & RUN DOWN TO 800', PUMPED WATER DOWN AND CIRCULATED, GOT ON THRU AND RAN TO 3325'. PULL TUBING OUT AND SANDED PERFS TO 3340' AND CAPPED WITH 4 SX'S CEMENT. ATTEMPTED TO CUT CASING AT 1500', 1100', AND 1000'. DID CUT OFF CASING AT 640' AND PULLED OUT OF HOLE. RUN TUBING BACK TO 1000' AND PUMP 35 SX'S WITH 2% CC AND 100#'S COTTON HULLS. PULL TUBING ON OUT AND LET SET FOR 1.5 HRS. TAGGED CEMENT WITH SAND BAILER AT 875'. PUMPED 35 SX'S WITH 2% CC AND COTTON HULLS THRU TUBING AT 550', PULL TUBING TO 260' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. TOPPED OFF WITH ANOTHER 3 SX'S CEMENT MIXED WITH WATER ON 7-2-15.

Perfs:

Top	Bot	Thru	Comments
3430	3440		CSG
3418	3428		CSG
3390	3400		CSG

Remarks: USED 190 SX'S COMMON CEMENT. QUALITY CEMENT #1835. WELL PLUGGED DUE TO DENIED TA - NO CURRENT OIL & GAS LEASE.

Plugged through: TBG

7/29/15 CKM

District: 02

Signed Virgil Clothier
(TECHNICIAN)

KCC WICHITA

JUL 14 2015

RECEIVED ✓✱