

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-02654-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 34-8S-16W
3708 feet from S Section Line, 2291 feet from E Section Line
Lease Name: HODSON A Well #: 4W
County: ROOKS Total Vertical Depth: 3361 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1274		
PROD	4.5	3360		175 SX
SURF	8.625	239		200 SX

Well Type: EOR UIC Docket No: E03504.6 Date/Time to Plug: 07/09/2015 1:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT, INC. Phone: (620) 793-5100

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/400 # hulls.
DV Tool at 1274' w/400 sx cement.
Production perforations: 3046' - 3322'

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/09/2015 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 4 1/2" casing and pumped 290 sx cement w/400 # hulls. Shut in pressure 400 psi.
Visually checked 8 5/8" x 4 1/2" annulus. Cement to surface.
GPS: 39.31725N -099.09357W

Perfs:

Top	Bot	Thru	Comments
3209	3322		

Remarks: GRESSEL OILFIELD SERVICES, LLC TICKET # 43375

Plugged through: CSG

7/29/15 ckm

District: 04

Signed

Pat Bedore

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

CM

JUL 16 2015

JUL 22 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

UIC ✓