

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-01000-00-01
Spot: NENESWNE Sec/Twnshp/Rge: 4-16S-10W
3675 feet from S Section Line, 1600 feet from E Section Line
Lease Name: HEITSCHMIDT Well #: 1
County: ELLSWORTH Total Vertical Depth: 3331 feet

Operator License No.: 6901
Op Name: D S & W WELL SERVICING, INC.
Address: 1822 24TH STREET
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3320		175 SX
SURF	8.625	319		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2015 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JIM LYMAN Company: DS & W WELL SERVICING INC Phone: (620) 793-5838

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/30/2015 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. RUN TUBING TO 3250' AND PUMP 25 SX'S CEMENT.
PERFORATE AT 1300', 950', AND 360'. RUN TUBING BACK TO 1300' AND PUMP 35
SX'S CEMENT WITH 3% CC. PULL TUBING TO 950' AND LET SET FOR 1 HOUR.
TAGGED CEMENT AT 1200' WITH SWAB BAR. PUMP 35 SX'S AT 950' THRU
TUBING, PULL TUBING TO 360' AND CIRCUALTE CEMENT TO SURFACE. PULL
TUBING OUT AND TOP OFF. USED APPROX. 245 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3302	3308		CSG

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET C 43340. LOG TECH OF KS. #8511.

Plugged through: TBG

7/29/15CKM

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

KCC WICHITA

JUL 14 2015

RECEIVED

1/24