

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19756-00-00
Spot: NW Sec/Twnshp/Rge: 1-25S-3E
660 feet from N Section Line, 440 feet from W Section Line
Lease Name: MCCRANER "C" Well #: 1
County: BUTLER Total Vertical Depth: 2717 feet

Operator License No.: 33974
Op Name: EAGLE CREEK RESOURCES, LLC
Address: PO BOX 377
SEWICKLEY, PA 15143

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6	2712		100 SX
SURF	15.5	62		100 SX
SURF	12.5	1145		
SURF	10	1395		
SURF	8	2140		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/08/2015 9:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: TYREL PHILLIPS Company: PHILLIPS WELL SERVICE Phone: (316) 621-0289

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/11/2015 10:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

6/8/2015. 1) DUG DOWN APPROX. 10-12 TO FIND SURFACE CSG., DID NOT LOCATE PIPE BUT FOUND CEMENT SUGGESTING 5.5" CSG WAS RAN AS A LINER AT AN UNKNOWN TIME. 2) RAN IN HOLE TO APPROX. 145' W/ POWER SWIVEL ON. CIRCUALTED RUBBER AND WOOD OUT OF HOLE. 6/9/2015. 1) RESUMED WASHING DOWN WELL W/ DRILL COLLARS. STILL CIRCUALTING CHIPS OF WOOD OUT OF HOLE. 2) RIG UP W/ MILL, MADE PROGRESS TO APPROX. 335' DOWN HOLE WHERE BRIDGED, CIRCUALTING METAL OUT. 6/10/2015 AT 1:00, MADE APPROX 4.5" OF PROGRESS SINCE PREVIOUS DAY, DECISION MADE TO PLUG AT THIS POINT. 6/11/2015 1) TUBING RAN IN HOLE TO APPROX 335'. 2) PUMPED 350 SKS OF CLASS A CEMENT (NO BLEND) WITH 2% CACL. 3) CEMENT CIRCUALTED UP 5.5" CASING AND THEN UP AROUND GROUND NEAR WELL INDICATING 15.5-5.5" ANNULAR SPACE FILLED W/ CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2713	2726	OH	

Remarks: CEMENTING COMPLETED BY CONSOLIDATED WELL SERVICES, EL DORADO, KS. TICKET #46154. PLUGGED DUE TO COMPLIANCE 82-3-111.

Plugged through: TBG

District: 02

Signed Jonathan Hill
KCC WICHITA (TECHNICIAN)

JUL 14 2015

RECEIVED