

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-29050-00-00
Spot: SENWNESW Sec/Twnshp/Rge: 4-26S-20E
2097 feet from S Section Line, 1855 feet from W Section Line
Lease Name: LU DLUM Well #: C2-4
County: ALLEN Total Vertical Depth: 1165 feet

Operator License No.: 34420
Op Name: EXODUS GAS & OIL LLC
Address: 1001 MCKINNEY ST., STE. 804
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		874		
PROD	5.5	1165		220 SX
SURF	8.625	22		5 SX
T1	2.875	1155		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/26/2015 12:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: RAY GILBERT Company: _____ Phone: (620) 820-9687

Proposed Plugging Method: Run tubing, cement to surface. Cut off casing and surface below plow depth. Cover and reseed when weather permits.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 06/23/2015 9:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 2 3/8" tubing down the inside of the 5.5" casing to 825'. Pumped and circulated cement from 825' to surface. Pulled the 2 3/8" tubing out of the well and topped the well off with cement. A total of 137 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
900	908		

RECEIVED
KCC DIST # 3
JUL 22 2015
CHANUTE, KS
RD

Remarks:

Plugged through: TBG

District: 03

Signed _____

KCC WICHITA

JUL 27 2015

RECEIVED

(TECHNICIAN)

7/29/15 CKM