

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-21190-00-00
Spot: E2NWNWNW Sec/Twnshp/Rge: 20-24S-17W
4986 feet from S Section Line, 4783 feet from E Section Line
Lease Name: CROSS JH Well #: 2-20
County: EDWARDS Total Vertical Depth: 4560 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4360		WITH 2 SX CMT
PROD	4.5	4552	0	WITH 225 SX CMT
SURF	8.625	265		WITH 210 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/26/2015 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ADAM APLEY Company: FG HOLL COMPANY Phone: (620) 793-0915

Proposed Plugging Method: CIBP @ 4360' WITH 2 SX CMT. PERFORATE @ 1220' & CIRCULATE CMT TO SURFACE. TIE ONTO BACKSIDE & CHECK.

Plugging Proposal Received By: WADE KLAUS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2015 12:45 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 4360' WITH 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATE AT 1220' & CIRCULATE CMT TO SURFACE WITH 345 SX CMT. TIE ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED UP TO 250-300#.

Perfs:

Top	Bot	Thru	Comments
4410	4418		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

7/29/15CPM

District: 01

Signed

Robert Dickerson

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JUL 10 2015

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
JUL - 2 2015
KCC DODGE CITY

JA

Form CP-2/3