

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-147-20632-00-00
Spot: W2NENWNW Sec/Twnshp/Rge: 18-4S-20W
330 feet from N Section Line, 740 feet from W Section Line
Lease Name: HOFAKER A Well #: 1
County: PHILLIPS Total Vertical Depth: 3715 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1720		185 SX
PROD	5.5	3712		150 SX
SURF	8.625	218		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/14/2015 9:00 AM
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.
Proposal Revd. from: DUANE EICHMAN Company: JOHN O. FARMER, INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement, 500 # hulls and 15 sx gel.
Production perforations: 3338' - 3532'
DV Tool at 1720' w/185 sx cement.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/14/2015 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3000' and pumped 15 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1750' and pumped 50 sx cement w/200 # hulls. Pulled tubing to 1250' and pumped 150 sx cement w/50 # hulls to circulate cement to surface. Pulled all tubing and topped off 5 1/2" casing w/20 sx cement. Hooked to 8 5/8" x 5 1/2" annulus. Pressured up immediately.

GPS: 39.71130N -099.62553W

Perfs:

Top	Bot	Thru	Comments
3526	3532		
3510	3515		
3498	3500		
3476	3478		
3338	3341		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1011

Plugged through: TBG

7/29/15 CKM

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUL 16 2015

JUL 22 2015

CONSERVATION DIVISION
WICHITA, KS