

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-26082-01-00  
Spot: SENWNW Sec/Twnshp/Rge: 28-18S-11W  
990 feet from N Section Line, 990 feet from W Section Line  
Lease Name: ROBL Well #: 1-29H  
County: BARTON Total Vertical Depth: 3182 feet

Operator License No.: 35147  
Op Name: GULF EXPLORATION, LLC  
Address: 9701 N. BROADWAY EXTENSION  
OKLAHOMA CITY, OK 73114

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3923		260 SX
SURF	9.625	482		200 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/08/2015 12:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: PAT MCGRAW Company: GULF EXPLORATION Phone: (405) 840-3380

Proposed Plugging Method: Ordered 33 sx gel, 400 sx 60/40 pozmix 4% gel cement and 400 # hulls.  
Horizontal Well  
TVD-3182' MTD-6365'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/09/2015 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

06/08/2015- Set CIBP at 3500' and topped with 2 sx cement. Ran tubing to 3400' and pumped 33 sx gel.  
06/09/2015- Cut casing at 1360'. Pulled one joint of casing and pumped 150 sx cement w/200 # hulls. Pulled casing to 960' and pumped 75 sx cement w/200 # hulls. Pulled casing to 480'. Circulated cement to surface with 160 sx cement. Pulled casing and topped off with 15 sx cement.  
GPS: 38.46122 -098.55096

Perfs:

Top	Bot	Thru	Comments
3821	6365		
3264	6365		

Remarks: ALLIED CEMENTING

Plugged through: CSG

District: 04

Signed Brian Ricketts  
(TECHNICIAN)

7/29/15 CKM

CM

KCC WICHITA

JUL 14 2015

RECEIVED

Form CP-2/3

JUN 10 2015