

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-25634-00-00  
Spot: NWSWNE Sec/Twnshp/Rge: 25-12S-19W  
1650 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: RUPP Well #: 1 "A"  
County: ELLIS Total Vertical Depth: 3870 feet

Operator License No.: 5046  
Op Name: RAYMOND OIL COMPANY, INC.  
Address: PO BOX 48788  
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3854		200 SX
SURF	8.625	219		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/22/2015 11:30 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: JAY JIMENEZ Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: Ordered 270 sx 60/40 pozmix 4% gel cement, 500 # hulls and 7 sx gel.  
Perforations: LKC, 3686' - 3690'  
Port Collar at 1590' w/400 sx cement.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/22/2015 2:30 PM KCC Agent: PAT STAAB

**Actual Plugging Report:**

Alliance ran in hole with tubing to 3599'. Allied rigged to tubing, mixed and pumped 7 sx gel followed by 50 sx cement w/100 # hulls mixed in. Pulled tubing to 2040' and pumped 150 sx cement w/200 # hulls to circulate cement to surface. Pulled tubing and topped off 4 1/2" casing with 20 sx cement. Hole standing full. Rigged to 8 5/8" casing and pumped 10 sx cement to pressure with 200 psi. Shut in pressure 100 psi.

GPS: 38.98231 -099.38032  
3629' FSL 2351' FEL  
NW NW SW NE

**Perfs:**

Top	Bot	Thru	Comments
3786	3796		
3775			
3712	3718		
3686	3690		


Received  
KANSAS CORPORATION COMMISSION  
**JUL 06 2015**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING CO. TICKET # 055667

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

CM

7/8/15 CKM

JUN 23 2015