

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-30158-00-00  
Spot: NESESE Sec/Twnshp/Rge: 34-15S-14W  
886 feet from S Section Line, 351 feet from E Section Line  
Lease Name: FIELD Well #: 1  
County: RUSSELL Total Vertical Depth: 3375 feet

Operator License No.: 31144  
Op Name: REDDIG ENTERPRISES INC.  
Address: 4325 177TH ST  
GORHAM, KS 67640

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3362		100 SX
SURF	8.625	263		165 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/29/2015 10:00 AM  
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.  
Proposal Rcvd. from: BRIAN REDDIG Company: REDDIG ENTERPRISES Phone: (785) 483-6170

Proposed Plugging Method: Bridged off at 450'. Drilled with pump and swivel. Went through bridge and ran pipe to bottom. All perforations on bottom zones have been squeezed off and have not been drilled out.  
Ordered 350 sx 60/40 pozmix 4% gel cement

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/29/2015 12:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1450', 920' and 250'. Ran tubing to 2700' and pumped 8 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1500' and pumped 60 sx cement w/100 # hulls. Pulled tubing to 900'. Circulated cement to surface with 90 sx cement. Pulled tubing and tied to casing. Circulated cement to surface on backside w/50 sx cement.  
GPS: 38.69927 -098.85804

Perfs:

Top	Bot	Thru	Comments
3362	3375		

Received  
KANSAS CORPORATION COMMISSION  
JUL 06 2015  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING  
Plugged through: TBG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

7/8/15 cpm  
CM

JUN 30 2015