

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-30296-00-00
Spot: SWSESE Sec/Twnshp/Rge: 34-15S-14W
284 feet from S Section Line, 770 feet from E Section Line
Lease Name: FIELD A Well #: 2
County: RUSSELL Total Vertical Depth: 3381 feet

Operator License No.: 31144
Op Name: REDDIG ENTERPRISES INC.
Address: 4325 177TH ST
GORHAM, KS 67640

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3371		100 SX
SURF	8.625	251		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/25/2015 10:00 AM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: BRIAN REDDIG Company: REDDIG ENTERPRISES Phone: (785) 483-6170

Proposed Plugging Method: Bridged off at 451'. Drilled with pump and swivel to 663'. Started to lock up and bring up pieces of metal. Will plug at 663'.
Ordered 250 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/25/2015 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 548' and pumped 100 sx cement. Circulated cement to surface on casing. Pulled tubing. Tied to casing and pumped 40 sx cement. Pressured to 200 psi and shut in. Tied to surface pipe and pumped 30 sx cement. Pressured to 200 psi and shut in.

GPS: 38.69762 -098.85952

Perfs:

Top	Bot	Thru	Comments
3371	3381		

Received
KANSAS CORPORATION COMMISSION
JUL 06 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

7/8/15 ckm

cm

JUN 30 2015