

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-057-20506-00-00
Spot: NESWSE Sec/Twnshp/Rge: 22-25S-21W
1002 feet from S Section Line, 1614 feet from E Section Line
Lease Name: NOLDE TWIN Well #: 1A
County: FORD Total Vertical Depth: 4825 feet

Operator License No.: 4067
Op Name: TKO INVESTMENTS, INC.
Address: 10881 W MCARTOR RD
DODGE CITY, KS 67801

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4724		
PROD	4.5	4824	0	WITH 150 SX CMT
SURF	8.625	665		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/22/2015 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: J DARYL TIEBEN Company: TKO INVESTMENTS Phone: (620) 225-0263

Proposed Plugging Method: PUMP 30 SX CMT WITH 50# HULLS. PERFORATE AT 1450' & PUMP 50 SX CMT WITH 50# HULLS. PERFORATE AT 700' & CIRCULATE CMT IN & OUT OF 4 1/2" CASING.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/22/2015 3:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

PUMPED 30 SX CMT WITH 50# HULLS PULLED TBG. PERFORATED AT 1450' & PUMPED 50 SX CMT WITH 50# HULLS. PERFORATED AT 700'. CIRCULATED CMT TO SURFACE WITH 250 SX CMT.

7-6-2015
Received
KANSAS CORPORATION COMMISSION
JUL 06 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

7/8/15

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
JUN 24 2015
KCC DODGE CITY