

1 080362

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C SE NW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,371-00-06
SEC. 14 T 29 S, R 12 W/E

3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6327 -5105
Kan-Ex sold to
Operator: Clarke Corporation
Name & Address: Box 187
Medicine Lodge, KS 67104

Lease Name Everitt Well # 1
County Pratt 156.65
Well Total Depth 4820 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 349

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105
Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 4:00 pm Day: 8 Month: April Year: 1985

Plugging proposal received from Elmo Morgenstert

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 4708' PBTD 4688' Perfs at 4459-67'

1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer
2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls
and 125 sx cement.

Plugging Proposal Received by J. A. Mey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:30 pm Day: 8 Month: April Year: 1985

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10
sx gel, 1 sack hulls and 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

APR 25 1985

Maximum pressure 900 psi and shut in 600 psi

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 3570' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-3-85

INV. NO. 7927

Signed J. A. Mey (TECHNICIAN)