

1 010201

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9427

Operator: Sharp Engineering Oil Operations
Name & Address: One Main Place, Suite 708
Wichita, KS 67202

API NUMBER 15-151-21,431-00-00

W/2 SW SW, SEC. 31, T 28 S, R 15 W/E
660 feet from S section line
4950 feet from E section line

Lease Name Whitney Well # "A" #1

County Pratt 153.69

Well Total Depth 4729 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 256

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 2:10 p.m. Day: 8 Month: 1 Year: 19 87

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 4729' PBTD 4713' Perfs at 4654-64' Elevation 2884' GL

1st plug sand back to 4600' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

and pump 120 sx cement.

Plugging Proposal Received by Don Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 8 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' and dumped 4 sx cement on top of sand
through bailer,

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

and pumped 120 sx cement.

STATE CORPORATION COMMISSION

Maximum pressure 550 psi and shut in 550 psi. 01-14-87 JAN 14 1987

Remarks: Recovered 2750' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton
(If additional description is necessary, use BACK of this form.)

(I did / XXXX) observe this plugging.

DATE 1-15-87

Signed Jack A. Ubel
(TECHNICIAN)

INV. NO. 15914