

To: 1 090054
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-15
API NUMBER 15- 151-21,084 - 58-50 169
NE NE-NE, SEC. 29, T 28 S, R 15 W/E
4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7105
Operator: Spines Exploration, Inc.
Name & Address 525 4th Financial Center
Wichita, KS 67202

Lease Name WBT Farms Well # 1
County Pratt 154.37
Well Total Depth 4750 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 428

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 2 p.m. Day: 15 Month: 2 Year: 19 91

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4750' w/225 sx cement, Perfs at 4599-4601'

1st plug sand back to 4450' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

and 100 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 15 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4450' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Maximum pressure 400 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2567' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

(if applicable) observe this plugging.

INVOICED

DATE 2-27-91

INV. NO. 30940

FEB 19 1991
02-19-91
CONSERVATION DIVISION
Wichita, Kansas

Signed [Signature]
(TECHNICIAN)