

1 080466

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,754-00-00
NE SE, SEC. 29, T 28 S, R 15 **W** **XX**

1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name Thompson 'W' Well # 1

Operator: Petroleum, Inc.

County Pratt 160.88

Name & Address 300 W. Douglas, Suite 800

Well Total Depth 4950 Arbuckle feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 347

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Woodman-Iannitti Drilling Co. License Number 5122

Address 704 Union Center Building, Wichita, KS 67202

Company to plug at: Hour: 1:30 pm Day: 23 Month: December Year: 1985

Plugging proposal received from Elmer Zimmerman

(company name) Woodman-Iannitti (phone) 316-265-7650

were: to fill hole with heavy mud and spot cement through drill pipe Elevation N/A
Anhydrite 960'

1st plug in the Arbuckle with 30 sx cement if 50' or more

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement
Plugging Proposal Received by J. H. Metz

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:00 pm Day: 23 Month: December Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 4890' with 30 sx cement, 2nd plug at 960' with 50

sx cement, 3rd plug at 380' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15

sx cement, 7th plug to circulate mouse hole with 10 sx cement. Plugged water well with

20 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan

(if additional description is necessary, use BACK of this form.)

INVOICED

(xxx) observed this plugging.

DATE JAN 07 1986

1-6-1986
JAN 6 1986

Signed J. H. Metz
(TECHNICIAN)

INV. NO. 11875

12-23 CONSERVATION DIVISION
Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date December 9 1985 month day year 11:10

API Number 15- 151-21,754-00-00 NW SE Sec. 29 Twp. 28 S, Rg. 15 East 1980 West 1980 Ft. from South Line of Section Ft. from East Line of Section

OPERATOR: License # 5238 Name Petroleum, Inc. Address 300 W. Douglas, Suite 800 City/State/Zip Wichita, KS. 67202 Contact Person Monte Chadd Phone 316 793-8471

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5122 Name Woodman-Iannitti Drilling Co. City/State 1022 Union Center, Wichita, Ks. 67202

Nearest lease or unit boundary line 660 feet County Pratt Lease Name Thompson 'W' Well # 1 Ground surface elevation feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Surface pipe by Alternate: 1 X 2 Depth to bottom of fresh water 215' Depth to bottom of usable water Permian Surface pipe planned to be set 300' Projected Total Depth 4950 feet Formation Arbuckle

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext. Air Rotary OWWO Expl X Wildcat Cable

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

cementing will be done immediately upon setting production casing. Date 12-9-85 Signature of Operator or Agent Title District Landman

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt. 2 This Authorization Expires 6-9-86 Approved By 12-9-85

1st if 50' in Arbuckle = 30 sby
2nd Base Anky w/ 50 sby
3rd 30' out of surf 60 sby
4th 40'-0' SB w/ 10 sby
15 sby nat 20 sby water well

RECEIVED STATE CORPORATION COMMISSION

JAN 6 1986