

To: 1 010049  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,285 - 00000 R

NW NW NW, SEC. 28, T 28 S, R 15 WXX  
4950 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6030  
Operator: Ainsworth Drilling Company  
Name & Address: P. O. Box 1269  
Colorado Springs, CO 80901

Lease Name Poovey Well # 1  
County Pratt 158.08  
Well Total Depth 4864 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8" feet 445

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893  
Address P. O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 11:00 am Day: 3 Month: December Year: 19 85

Plugging proposal received from Bruce Warner

(company name) Pratt Well Service (phone) 316-672-2531

were: 5 1/2" at 4862' PBD 4530' Perfs at 4501-4507'

1st plug sand back to 4451' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 115 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:25 am Day: 3 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4490' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pumped 115 sx cement.

Maximum pressure 600 psi and shut in 200 psi

Remarks: Recovered 2225' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE DEC 16 1985

INV. NO. 11518

12-3

RECEIVED  
STATE CORPORATION COMMISSION  
12-5-1985  
DEC 5 1985

Signed

*Richard W. Lacey*  
(TECHNICIAN)