

1 010048

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,325-00-00 **R**

SE NW NW, SEC. 28, T 28 S, R 15 **(W/E)**  
4290 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6030  
Operator: Ainsworth Drilling Company  
Name & Address: P. O. Box 1269  
Colorado Springs, CO 80901

Lease Name Poovey Well # 2  
County Pratt 158.60  
Well Total Depth 4880 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 457

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893  
Address P. O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 1:00 pm Day: 3 Month: December Year: 19 85

Plugging proposal received from Bruce Warner  
(company name) Pratt Well Service (phone) 316-672-2531

were: 5 1/2" at 4878' PBTD 4618' Perfs at 4612' 4614'

1st plug sand back to 4462' and dump 5 sx cement on top of sand through bailer  
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 115 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:25 pm Day: 3 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4460' and dumped 5 sx cement on top of  
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10  
sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 115 sx cement.

Maximum pressure 800 psi and shut in 400 psi

Remarks: Recovered 1860' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE DEC 16 1985  
INV. NO. 11517  
12-3

RECEIVED  
STATE CORPORATION COMMISSION  
Signed

DEC 5 1985  
12-5-1985  
CONSERVATION DIVISION

*[Signature]*  
(TECHNICIAN)