

1 020302

2-26

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,287,000
100' W of C
NW NE, SEC. 4, T 28 S, R 20 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4243
Operator: Cross Bar Petroleum, Inc.
Name & Address: P.O. Box 20080
Wichita, KS 67208

4620 feet from S section line
2080 feet from E section line
Lease Name Zimmerman B Well # 1
County Kiowa 166.40
Well Total Depth 5120 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 437

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Eagle Drilling, Inc. License Number 5380
Address 2759 South Broadway, Wichita, KS 67216

Company to plug at: Hour: 6 p.m. Day: 26 Month: 2 Year: 19 90

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling, Inc. (phone) 316-945-9935

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1309'
Elevation 2305'

1st plug at 1310' with 50 sx cement, 2nd plug at 460' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:30 p.m. Day: 26 Month: 2 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1310' with 50 sx cement,

2nd plug at 460' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO.
(If additional description is necessary, use BACKLOG FORMS form.)

observe this plugging.

INVOICED

DATE 3-14-90

INV. NO. 27634

Signed Glenn R. Barlow (TECHNICIAN)

RECEIVED

MAR 12 1990

EFFECTIVE DATE: 2/11/90

Must be approved by the K.C.C. five (5) days prior to commencing well

100' C NW NE

Expected Spud Date FEBRUARY 18 1990

Sec 4 Twp 28S S, Rg 20 East West

OPERATOR: License # 4243
Name: CROSS BAR PETROLEUM, INC.
Address: P.O. BOX 20080
City/State/Zip: WICHITA, KANSAS 67208
Contact Person: ALBERT BRENSING
Phone: 316/799-2933

4620 feet from South line of Section
2080 feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 5380
Name: EAGLE DRILLING, INC.

County: KIOWA
Lease Name: ZIMMERMAN B Well #: 1
Field Name: FRALICK West
Is this a Prorated Field? yes X no
Target Formation(s): MISSISSIPPIAN
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 2305' feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 100'
Depth to bottom of usable water: 247'
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 400'
Length of Conductor pipe required: NONE
Projected Total Depth: 5200'
Formation at Total Depth: MISSISSIPPIAN
Water Source for Drilling Operations: well farm pond X other

Well Drilled For: Well Class: Type Equipment:
X Oil Inj Infield X Mud Rotary
X Gas Storage Pool Ext. Air Rotary
OAWO Disposal X Wildcat Cable
Seismic; # of Holes

If OAWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

AFFIDAVIT Exp. 8/6/90
W.A.S. 2-26-90

260' Alt. I Req.

The undersigned hereby affirms that the drilling completion...

PUSHER Butch Steinert.
TD 5120 FORMATION M15 S
SURFACE PIPE @ 437
ANHYDRITE 1309 ELEVATION 2305
STARTING TIME & DATE 6:30 2-26-90
COMPLETION TIME & DATE 8:30 PM
1st PLUG @ 1310 FT. W/ 50 SX
2nd PLUG @ 460 FT. W/ 40 SX
3rd PLUG @ 40 FT. W/ 10 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY HOWCO
TECHNICIAN 2-26-90 G.B.
TYPE OF CEMENT 60/40 (eye)el

Spud 2-19-90
+ 400 surf
water well

RECEIVED

Table with depth markers: 5280, 4950, 4620, 4290, 3960, 3630, 3300, 2970, 2640, 2310, 1980, 1650, 1320, 990, 660, 330

MAR 12 1990

- REMEMBER TO: CONSERVATION DIVISION Wichita, Kansas
- File Drill Pit Application (form CDP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- File acreage attribution plat according to field proration orders;
- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.