

1051704

7-30

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-21,341 - 0000  
NE NW SE, SEC. 3, T 28 S, R 20 W/E  
2310 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4243

Lease Name Liggett Well # 3-1

Operator: Cross Bar Petroleum, Inc.

County Kiowa

Name & Address 220 W. Douglas, Ste. 140

Well Total Depth 5300 172.25 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 467

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10 a.m. Day: 30 Month: 7 Year: 1993

Plugging proposal received from Fred Mease

(company name) Pratt Well Service Inc. (phone) 316-672-2531

logs: 5 1/2" at 5299' w/200 sx cement, PBTB 5246', CIBP at 4425', 4345', Perfs at 4912-15, 4385-89, 4310-20'

1st plug sand back to 4250' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 30 Month: 7 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4250' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released

8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3108' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

1 (did / ~~XXXXXX~~ observe this plugging.

INVOICED  
DATE 8-9-93  
INV. NO. 38279

Signed Richard W. Lusk  
STATE CORPORATION COMMISSION  
RECEIVED  
AUG - 9 1993  
CONSERVATION DIVISION  
WICHITA, KANSAS