

To: 1 010124  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,097-<sup>901</sup>0000

NW NW NW, SEC. 3, T 28 S, R 20 W/E

4950 feet from S section line

4950 feet from E section line

Lease Name Brensing C Well # 1

County Kiowa 159.58

Well Total Depth 4910 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 598

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

Operator: J. Mark Richardson

Name &

Address 640 Century Plaza Building

Wichita, KS 67202

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:35 am Day: 10 Month: April Year: 19 86

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers (phone) 316-793-9721

were: 4 1/2" at 4909' PBTD 4905' Perfs at 4896-4899'

1st plug pump 1 sack hulls and 20 sx cement to 4800'

2nd plug squeeze well with 3 sx hulls, 10 sx gel 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 am Day: 10 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 30 sx common cement to 4800'.

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement. Pumped water well with 10 sx common cement.

Maximum pressure 800 psi and shut in 600 psi. Used common cement by Halliburton

Remarks: Recovered 1987' 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED  
APR 15 1986

APR 15 1986

Signed

Steve Durrant  
(TECHNICIAN)

DATE \_\_\_\_\_

INV. NO. 13456

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84