

10-11 15-057-10004-0600, 27R

To: 1 051485  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drilled in 1958  
C SE NW, SEC. 24, T 28 S, R 21 W/4  
3300 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5134  
Operator: Graham-Michaelis Corporation  
Name & Address: P.O. Box 247  
Wichita, KS 67201

Lease Name Toner Well # 1  
County Ford 167.53  
Well Total Depth 5155 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 413

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 3 p.m. Day: 11 Month: 10 Year: 19 91

Plugging proposal received from Elmo Morgenstern  
(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 5154' w/150 sx cement, Perfs at 5048-60'  
1st plug pump 1 sx hulls and 20 sx cement,  
2nd plug pump 3 sx hulls, 20 sx cement, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,  
and 150 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 4:40 p.m. Day: 11 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement to bottom (didn't hold).  
Sanded back to 5000' and dumped 5 sx cement on top of sand through bailer,  
2nd plug pumped 300 lbs. hulls, 20 sx cement, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls and 150 sx cement.

Maximum pressure 700 psi and shut in 500 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 22 1991

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3000' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
(old procedure) observe this plugging.

DATE 10-30-91  
INV. NO. 33548

Signed Richard W. Tracy  
(TECHNICIAN)