

3-27 170 R

To: 1 051284
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
300 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-057-20,481-0000
C. NE, SEC. 24, T. 28 S, R. 21 W/E
3870 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30034
Operator: Zinke + Trumbo Ltd
Name & Address 1202 E 33rd St
Suite 100
Tulsa, OK 74105

Lease Name Hayse Well # 1-24
County Ford 190.13
Well Total Depth 5850 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 667

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling Inc License Number 5422

Address 801 Union Center Bldg Wichita, KS 67202

Company to plug at: Hour: 4:00 pm Day: 27 Month: March Year: 1990

Plugging proposal received from David Rice

(company name) Zinke + Trumbo Ltd (phone) 918-743-5096

were: ~~1st~~ to fill hole with Heavy mud + spot 2 plugs through Drill pipe
1st plug @ 5700' with 40sx cement Rat hole + ^{Mousehole} circulated with 15sx
2nd plug @ 1350 with 50sx cement company was the going to pump
to pit down the surface pipe. Then pump ~~down~~ 155sx cement
down the surface pipe

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 6:30p Day: 27 Month: March Year: 1990

ACTUAL PLUGGING REPORT 1st plug @ 5700' with 40sx through Drill pipe

Abercrombie misplaced second plug @ 600'. Operator had to
drill out 600' plug to pump the pit down the surface pipe
Company operator pumped a 6000 bbl of Mud down surface. Then pumped
50 sx cement, 10%el 15x hells and 155sx cement down 8 5/8 casing
Rat hole + ~~M~~circulated w 15 sx Mousehole circulated with 10 sx.

Remarks: Used 60/40 poz mix 60% gel by BJ titan Max pres. 500 psi shut in 300psi
(if additional description is necessary, use BACK of this form.)

INVOICED

STATE CORP. observe this plugging. 1990

DATE 4-9-90

INV. NO. 27822

CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacey
(TECHNICIAN)