

To: 1.060145 9-16  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,509-0000 166R  
C E/2 SE, SEC. 23, T. 28 S, R. 21 W/E  
1320 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30269  
Operator: Argent Energy, Inc.  
Name & Address: 110 S. Main, Suite 510  
Wichita, KS 67202-3745

Lease Name G. Smith Well # 1  
County Ford 167.70  
Well Total Depth 5160 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 634

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A   
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company, Inc. License Number 30606  
Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 2 a.m. Day: 16 Month: 9 Year: 1992

Plugging proposal received from Bill Wynn  
(company name) Murfin Drilling Company, Inc. (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe  
1st plug at 1450' with 50 sx cement, 2nd plug at 670' with 60 sx cement,  
3rd plug at 40' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 4:15 a.m. Day: 16 Month: 9

TECHNICIAN RECEIVED  
STATE CORPORATION COMMISSION  
SEP 2 1992  
Year: 1992  
CONSERVATION DIVISION  
Wichita, Kansas  
9-21-1992

ACTUAL PLUGGING REPORT 1st plug at 1450' with 50 sx cement,  
2nd plug at 670' with 60 sx cement,  
3rd plug at 40' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 10-9-92  
INV. NO. 36398

Signed \_\_\_\_\_ (TECHNICIAN)

EFFECTIVE DATE: 9-9-92

State of Kansas

FORM MUST BE TYPED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL 057-20,509-000

FORM MUST BE SIGNED

SEA7: X Yes... No

Must be approved by the K.C.C. five (5) days prior to commencing well

ALL BLANKS MUST BE FILLED

Expected Spud Date September 7 1992

Spot VC E/2 SE Sec 23 Twp 28 S. Rg 21 East West

OPERATOR: License # 30269 Argent Energy, Inc. 110 South Main, Suite 510 Wichita KS 67202-3745 James C. Remsberg 316/262-5111

1320 feet from South / XXXX line of Section 660 feet from East / XXXX line of Section IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License # 30606 Murfin Drilling Company, Inc.

County: Ford Lease Name: G. Smith Well #: 1 Field Name: Pleasant Valley

Is this a Prorated/Spaced Field? yes X no

Target Formation(s): Mississippian

Nearest lease or unit boundary: 660'

Ground Surface Elevation: 2370 feet MSL

Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 145

Depth to bottom of usable water: 380

Surface Pipe by Alternate: X 1 2

Length of Surface Pipe Planned to be set: 600

Length of Conductor pipe required: NONE

Projected Total Depth: 5150

Formation at Total Depth: Mississippian

Water Source for Drilling Operations: well farm pond X other

DWR Permit #:

Will Cores Be Taken?: yes X no

If yes, proposed zone:

Well Drilled For: Well Class: Type Equipment: Oil Enh Rec X Infield X Mud Rotary X Gas Storage Pool Ext. Air Rotary OWD Disposal Wildcat Cable Seismic: # of Holes Other

If OWD: old well information as follows:

Operator: Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no

If yes, true vertical depth:

Bottom Hole Location:

400' Alt. I Req.

AFFIDAVIT

Exp. 3/4/93

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well...

STATE RECEIVED SEP 21 1992 CONSERVATION DIVISION Wichita, Kansas

Pusher Bill Wynn SPUD DATE 9-8-92 INIT. DW LENGTH SURFACE PLANNED 600' RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 6 3/4" CONDUCTOR ANHYDRITE T- B- ELEVATION TD 5160 FORMATION Miss RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 1450 Ft. W/ 50 SX 1/2 Base Anyh. @ 670 Ft. W/ 60 SX 1/2, 1/2 Plug @ Ft. W/ SX Bottom Surface @ Ft. W/ SX 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN Ch DATE 9-14-92 TYPE OF CEMENT 60/40 620 1/4# STARTING TIME 2:00 (AM/PM) DATE 9-15-92 COMPLETION TIME 4:15 (AM/PM) DATE 9-15-92 CEMENT COMPANY Allied