

To: 1 051484
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT
Operator License # 5134
Operator: Graham-Michaelis Corporation
Name & Address P.O. Box 247
Wichita, KS 67201

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____
Plugging Contractor Clarke Corporation
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1 p.m. Day: 11 Month: 10 Year: 19 91
Plugging proposal received from Elmo Morgenstern
(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 5099' w/200 sx cement, Perfs at 5040-5060'
1st plug pump 1 sx hulls and 20 sx cement to bottom,
2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 2:30 p.m. Day: 11 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement to bottom (didn't hold).
Sanded back to 4990' and dumped 5 sx cement on top of sand through bailer,
2nd plug pumped 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.
Maximum pressure 400 psi and shut in 250 psi.

RECEIVED
STATE CORPORATION COMMISSION

OCT 22 1991

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2500' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-30-91
INV. NO. 33549

Signed Richard W. Tracy
(TECHNICIAN)