

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

1051996

12-29

API NUMBER 15- 057-20,167-0000

N/2 SE, SEC. 14, T 28 S, R 21

1980 feet from S section line

1320 feet from E section line

Lease Name Vice Well # 1

County Ford

Well Total Depth 5160 167.70 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 620

TECHNICIAN'S PLUGGING REPORT

Operator License # 7118

Operator: Seagull Operating Co. Inc.

Name:

Address 416 Traffis, Ste. 1215

Shreveport; LA 71101

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address 107 W. Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:30 P.m. Day: 29 Month: 12 Year: 19 95

Plugging proposal received from Allen Vratil

(company name) Clarke Corporation (phone) 316-886-5665

logs: 4 1/2" at 5159' w/150 sx cement, PBSD 5071', Perfs at 5044-46'

1st plug sand back to 5000' and dump 4 sx cement on stop of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 175 sx cement.

STATE CORPORATION COMMISSION

JAN 9 1996

1-4-1996

STATE CORPORATION COMMISSION

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 P.m. Day: 29 Month: 12 Year: 1995

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5000',

2nd plug pumped down the 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 175 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3600' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 09 1996

INV. NO. 44464

observe this plugging.

Signed Richard W. Lucy (TECHNICIAN)