

1051787

3-10

API NUMBER 15- 057-20,184-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW NE, SEC. 14, T. 28 S, R. 21 W/8
4950 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7016

Lease Name Vibe Well # 2

Operator: Seagull Operating Co., Inc.
Name: Seagull
Address: 416 Traffis St., Ste. 1216
Freeport, LA 71101

County Ford

Well Total Depth 5140 167.05 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 667

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 10 a.m. Day: 10 Month: 3 Year: 19 94

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

was: 4 1/2" at 5138' w/225 sx cement, Perfs at 5041-44'

1st plug pump 100 lbs. hulls and 30 sx cement, displace to 4800',

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, and 175 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 10 Month: 3 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 100 lbs. hulls and 30 sx cement, displaced to 4800',

2nd plug pumped 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, and 175 sx cement.

Maximum pressure 700 psi and shut in 400 psi.

RECEIVED
STATE CORPORATION COMMISSION

MAR 15 1994

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 4000' of 4 1/2" casing.

INVOICED (if additional description is necessary, use BACK of this report.)

(I did / ~~did not~~ observe this plugging.)

DATE MAR 29 1994

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 40180