

1 060784

API NUMBER 15- 057-20,191-~~6000~~ ³⁴¹ R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C E/2 NE SW, SEC. 14, T 28 S, R 21 W/4
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1980 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Mann "B" Well # 2

Operator: TXO Production Corporation
Name & Address: 155 North Market, Suite 1000
Wichita, KS 67202

County Ford 1/6/86

Well Total Depth 5165 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 625

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P. O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 9:00 am Day: 27 Month: January Year: 19 86

Plugging proposal received from Jerry Pritchard

(company name) TXO (phone) 316-269-7600

were: 2 7/8" at 5164' PBTD 5132' Perfs at 5044-50'

1st plug pump 10 sx cement to bottom

2nd plug circulate from 625' to surface through 2 7/8"

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45 pm Day: 29 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1-27-86 - 1st plug pumped 10 sx cement through 2 7/8" to bottom covering the perfs. Perforated the 2 7/8" production casing at 700'. Pumped 250 sx cement.

Ran wire line on annulus. Had fluid at 250' and topped cement at 700'. 1-29-86 - Cement fell to 700' - no fluid in the hole. Pumped 190 sx cement through head with 1 sack hulls mixed into the first few sx cement. Cement filled hole to surface.

RECEIVED
STATE CORPORATION COMMISSION
FEB 4 1986

Remarks: No Recovery. Used 50/50 Pozmix by Halliburton.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, KS 2-4-1986

INVOICED observe this plugging.

Signed Paul A. Luthie (TECHNICIAN)

DATE FEB 6 1986
INV. NO. 12422