

To: 1 060785
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,408-0000
NW NE SW , SEC. 14 , 'T 28 S, R 21 W/EX

2360 feet from S section line
3590 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Mann "B" Well # 3

Operator: TXO Production Corp.
Name & Address 155 N. Market, Suite 1000
Wichita, KS 67202

County Ford 169.00

Well Total Depth 5200 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 649

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Oilfield Services License Number 5105

Address 107 W. Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:15 am Day: 27 Month: January Year: 19 86

Plugging proposal received from Jerry Pritchard

(company name) TXO (phone) 316-269-7600

were: 4 1/2" at 5199' PBD 5050' Perfs at 5036-38'

1st plug sand back to 4940' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 170 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00 am Day: 27 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4940' and dumped 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10
sx gel, 1 sack hulls and 170 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1986

Maximum pressure 600 psi and shut in 450 psi

Remarks: Recovered 2534' 4 1/2" casing. Used 50/50 Pozmix by Halliburton.
(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
1-30-1986

INVOICED
(if additional description is necessary, use BACK of this form.) observe this plugging.

Signed Paul A. Luthie
(TECHNICIAN)

DATE JAN 31 1986

INV. NO. 12222