

LEASE NAME Ross

WELL NUMBER 1

1978 Ft. from S Section Line
510

 Ft. from E Section Line

SEC. 7 TWP. 28S RGE. 15W (E) or (W)

COUNTY Pratt

Date Well Completed 11-21-84

Plugging Commenced 8-10-92

Plugging Completed 8-20-92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR VAL Energy, Inc.

ADDRESS Box 322 Haysville, Ks. 67060

PHONE# (316) 522-1560 OPERATORS LICENSE NO. 5822

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-10-92 (date)

by Dodge City, Ks. (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Miss Depth to Top 4634 Bottom 4684 4684

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	water	0	473	8 5/8	473	none
	water	0	4684	4 1/2	4792	3194

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s
Sand back to 4575 spot 4 sx cement, pull pipe at 3194, pump 300 lbs.
hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1sx hulls, wiper plug
150 sx 60/40 6% gel. Shut in 300 psi. 8/20/92 3:00 PM Allied #3123

Name of Plugging Contractor VAL Energy, Inc. License No. 5822

Address Box 322 Haysville, Ks. 67060

RECEIVED
 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: VAL Energy, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

AUG 21 1992

K. Todd Allam (Employee of Operator) or Operator

above-described well, being first duly sworn on oath, says: That I have knowledge of the fac statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.

(Signature) K. Todd Allam

(Address) Wichita, Ks.

SUBSCRIBED AND SWORN TO before me this 20 day of August, 19 92

Gary D. Stearns
 Notary Public

USE ONLY ONE SIDE OF EACH FORM

