

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-151-21,671-60-08

LEASE NAME BAKER

WELL NUMBER 1

3630 Ft. from S Section Line

4520 Ft. from E Section Line

SEC. 21 TWP. 28 RGE. 15 ~~Y~~ or (W)

COUNTY PRATT

SPUD DATE:

Date Well Completed 8-19-85

Plugging Commenced 6-20-91

Plugging Completed 6-22-91

LEASE OPERATOR PRATT WELL SERVICE, INC.

ADDRESS P. O. BOX 847 PRATT, KS. 67124

PHONE# (316) 672-2531 OPERATORS LICENSE NO. 5893

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on BOTTOM HOLE: 3-26-91 TOP HOLE: 6-24-91 (date)

by DUANE RANKIN AND RICHARD LACEY (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation PERES: Depth to Top _____ Bottom _____ T.D. _____

4717-24; 4665-69; 4648-52; 4626-29; 4648-50; 4826-32; 4614-19;

Show depth and thickness of all water, oil and gas formations.

RECEIVED
 STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

JUL 02 1991

Formation	Content	From	To	Size	Put in	Pulled out
		0	476	8 5/8	476	0
		0	4930	5 1/2	4930	2505 ft - 59 jts.

CONSERVATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
6-20-91: PUMPED SAND TO 50 FT. ABOVE PERES, PLUS 5 SX CEMENT. 6-22-91: CUT AND PULLED 59 JTS PLUS 10 FT OF CUT OFF JOINTS=2505 FT. 6-24-91: TOP HOLE PLUG: 300# HULLS, 10 GEL, 50 SX CEMENT, 10 GEL, 100 # HULLS, 8 5/8 PLUG, 100 SX CEMENT, 60-40 POZ, 6% GEL. 500 MAX, 300 ISIP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KANSAS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PRATT WELL SERVICE, INC.

STATE OF KANSAS COUNTY OF PRATT, ss.


JUDY BERRY

PLUGGING CONTRACTOR

(Employee of ~~Pratt Well Service, Inc.~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Pratt, Kans. Pratt, Ks.



SUBSCRIBED AND SWORN TO before me this 1st day of July, 19 91

Dorothy M. Ferguson
 Notary Public

My Commission Expires: February 6, 1993