

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21718-00-00

LEASE NAME Hughes-Gross

WELL NUMBER #2

SPOT LOCATION C NW NW

SEC. 19 TWP 28S RGE. 15 (W)

COUNTY Pratt

Date Well Completed 10-12-85

Plugging Commenced 3:15 a.m.
10-13-85

Plugging Completed 5:15 a.m.
10-13-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Plano Petroleum Corporation

ADDRESS P.O. Box 247, Plano, Texas 76074-0040

PHONE # () OPERATORS LICENSE NO.

Character of Well Dry Hole
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Paul Luthie - Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached? log is attached

Producing formation Depth to top bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	8 5/8"	-0-	309	7 jts	23 wt new	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Well plugged as follows: 50 sks @ 1000', 50 sks @ 340', 10 sks @ 40', 15 sks Rathole
10 sks Mousehole, 10 sks water well.
145 sks of cement, 60/40 POZ, 6% gel.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B.J. Titan License No.
Address Medicine Lodge, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.


Plano Petroleum Corporation (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Wayne L. Kirkman,
President
(Address) P.O. Box 18611, Wichita, KS 67218

SUBSCRIBED AND SWORN TO before me this 16th day of October, 1985

RECEIVED
STATE OF KANSAS
NOTARY PUBLIC
Kirkman

OCT 17 1985




June 12, 1989

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4 1-84
Revised 06-83

ALDEBARAN

453 SOUTH WEBB ROAD
P.O. BOX 18611
WICHITA, KANSAS 67207
(316) 685-5372



DRILLING CO. INC.

W E L L L O G

WELL NAME: HUGHES-GROSS #2

WELL LOCATION: C NW NW

Section 19-28S-15W, Pratt County, K

OPERATOR: Plano Petroleum Corporation

COMMENCED: 10-3-85

CONTRACTOR: Aldebaran Drilling Co., Inc.

COMPLETED: 10-12-85

CASING RECORD: 7 Jts. of 8 5/8"

new set at 309', 200 sks Class A,
3% gel, 2% cc.

FORMATION:

FROM:

TO:

Sand & Red Bed	-0-	241'
Red Bed	241'	1095'
Red Bed, Shale & Lime	1095'	2117'
Shale	2117'	2330'
Lime & Shale	2330'	3381'
Bern	3381'	3478'
Lime & Shale	3478'	4600'
Mississippi	4600'	4682'
Lime & Shale	4682'	4770'

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED
C NW NW Section 19-28S-15W, Pratt County, Kansas TO THE BEST OF MY
KNOWLEDGE AND BELIEF.

ALDEBARAN, DRILLING CO., INC.

SUBSCRIBED AND SWORN TO BEFORE ME THIS 16th DAY OF October, 1985

MY APPOINTMENT EXPIRES:

June 12, 1989



RECEIVED

STATE CORPORATION COMMISSION

OCT 17 1985

Lynanne T. Rohlman

NOTARY PUBLIC

CONSERVATION DIVISION
Wichita, Kansas