

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pratt County. Sec. 15 Twp. 28S Rge. 15 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C SE SE


Lease Owner Imperial Oil Company  
Lease Name Vaught Well No. 1-15  
Office Address 720 Fourth Financial Center, Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole

Date Well completed Oct. 5 1978  
Application for plugging filed (verbally) Oct. 5 1978  
Application for plugging approved (verbally) Oct. 5 1978  
Plugging commenced Oct. 5 1978  
Plugging completed Oct. 5 1978

Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens  
Producing formation Depth to top Bottom Total Depth of Well 4730'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set 1st plug at 540' with 50 sacks  
2nd plug at 360' with 40 sacks  
3rd plug at 40' with 1/2 sack hulls & 12 sacks cement  
3 sacks in rathole  
Cemented with 50-50 posmix, 6% gel.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Jack L. Partridge, Ass't. Secretary-Treasurer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of October, 1978

Sandra Richman  
Sandra Richman Notary Public.

My commission expires July 21, 1979

RECEIVED  
STATE CORPORATION COMMISSION

OCT 13 1978  
10-13-1978  
CONSERVATION DIVISION  
Wichita, Kansas



CONTRACTOR'S WELL LOG

OPERATOR: Imperial Oil Company  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Vaught #1-15  
 LOCATION: C SE SE Section 15-28S-15W  
 Pratt County, Kansas  
 SPUD DATE: September 25, 1978  
 COMPLETION DATE: October 5, 1978

0	42	Surface soil & sand
42	361	Sand & shale
361	1582	Red bed & shale
1582	2374	Shale & lime
2374	2968	Lime & shale
2968	3526	Shale & lime
3526	4567	Lime & shale
4567	4590	Lime, shale & chert
4590	4730	Lime & shale
	4730	Rotary Total Depth

SAMPLE TOPS:

Anhydrite 941' (+1137)  
 B/Anhydrite 960' (+1118)

Spud hole at 2:30 p.m., September 25, 1978. Drilled 361' of 12½ hole. Ran 9 joints of 8-5/8"--20# surface casing. Set at 361' with 175 sacks of lite, 3% CaCl, followed with 125 sacks of common, 3% CaCl. Cement did circulate. Plug was down at 9:30 p.m., September 25, 1978.

T.D.4730'. Set first plug at 540' with 50 sacks, second plug at 360' with 40 sacks, third plug at 40' with 1/2 sack hulls and 12 sacks cement, rathole with 3 sacks. Cemented with 50-50 posmix, 6% gel. Plug was down at 10:15 p.m., October 5, 1978. State Plugger - Bill Owens.

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )


Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Vaught #1-15, C SE SE Section 15-28S-15W, Pratt County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge,  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 11th day of October, 1978.

Sandra Richman  
 Sandra Richman, Notary Public



RECEIVED  
 STATE CORPORATION COMMISSION

OCT 13 1978

CONSERVATION DIVISION  
 Wichita, Kansas