

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,978 - 00-00

LEASE NAME Dallas-Keller

WELL NUMBER #1-15

3960 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 15 TWP. 29 RGE. 12(E) or (W)

COUNTY Pratt

Date Well Completed 2-3-90

2-3-90

Plugging Commenced 7:00 PM

2-3-90

Plugging Completed 9:00 PM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl Company

ADDRESS P. O. Box 780167, Wichita, Kansas 67278-0167

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well dry hole

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-2-90 (date)

by Mike Willson (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4720

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	312'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Filled hole with heavy mud, plugged with 50 sacks 170' up to 621', 40 sacks 340' up to 222', 15 sacks 60' to surface, 15 sacks in rathole. Used 60/40 Pozmix W/ 6% gel by Halliburton Service.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129, Sterling, Kansas 67579

STATE OF Kansas COUNTY OF Rice, ss.

Richard L. Mead

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION

(Signature) Richard L. Mead

(Address) P.O. Box 129, Sterling, Ks 67579

FEB 8 1990 2-8-1990
SUBSCRIBED AND SWORN TO before me this 5 day of February, 19 90

CONSERVATION DIVISION
Wichita, Kansas

My Commission Exp



F.A. Wuellner
Notary Public F.A. Wuellner

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- Dallas-Keller 1-15
C NE/4, Sec. 15-T29S-R12W, Pratt County, Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 26, 1990

COMPLETED: February 3, 1990

TOTAL DEPTH: 4720'

LOG

0' - 200'	Sand & clay
200' - 315'	Red Bed
315' - 1090'	Shale & Red Bed
1090' - 4720'	Lime & Shale

CASING RECORD

Ran 7 joints 8 5/8" 23# new casing.
299.41' pipe set at 312' KB. Cemented
with 225 sacks 60/40 Pozmix W/ 2%
Gel & 3% cc. Plug down at 12:30PM
1-26-90 by Howco. Good returns to
surface.

Plugged February 3, 1990

DEVIATION SURVEYS

4300' - 1°
4472' - 3/4°
4720' - 1 1/4°

RECEIVED
STATE CONSERVATION COMMISSION

FEB 8 1990

CONSERVATION DIVISION
Wichita, Kansas