

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pratt County. Sec. 13 Twp. 29 Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner Rupp-Ferguson Oil Co.

Lease Name Thompson Well No. 1

Office Address 523 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-16-56 19

Application for plugging filed 7-16-56 19

Application for plugging approved 7-16-56 19

Plugging commenced 7-16-56 19

Plugging completed 7-16-56 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4710 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	370	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 360, plug, hulls, 25 sacks cement thru d.p. Mud to 35', plug, hulls, cement to cellar base.

RECEIVED
STATE CORPORATION COMMISSION

07-21-56 JUL 21 1956

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rupp-Ferguson Oil Co.

Address 523 Petroleum Bldg., Wichita, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

L. W. Knox (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. W. Knox

523 Petroleum Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of July, 19 56

Helen Horine

Notary Public.

My commission expires June 4, 1959

PLUGGING
FILE SEC. 13 T. 29 R. 12W
BOOK PAGE 81 LINE 29

CONTRACTOR'S WELL LOG

Rupp-Ferguson No. 1 Thompson
NE NE SW, Sec. 13-29-12W,
Pratt County, Kansas

Set 370' of 8 5/8" surface casing
w/200 sacks cement.

Contractor: Rupp-Ferguson Oil Co.
Commenced: 6-28-56
Completed: 7-16-56 D & A

Elev. 1886 KB

Figures Indicate Bottom of Formation

65 soil
70 sand
80 clay
230 sand
290 red bed
335 Anhydrite
685 red bed
980 red bed & shale
1555 shale, shells & salt
1760 shale & shells
1830 lime & shale
1855 lime
3446 lime, shale
3610 lime
3692 lime, shale streaks
3755 lime & shale
3827 lime, shale & sand
3845 sandy shale
3900 lime & shale
4014 lime
4109 lime & shale
4315 lime
4320 Miss.
4373 chert & shale
4427 shale
4489 Kinderhook
4578 Viola
4601 lime, shale & sand
4696 Simpson
4710 Arb., T.D.

RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1956

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK - SS:

I, L. W. Knox, landman for Rupp-Ferguson Oil Co., do hereby certify that the above and foregoing is a true and correct copy of the log of the No. 1 Thompson well.

L. W. Knox
L. W. Knox

Subscribed and sworn to before me this 20th day of July, 1956.

Helen Horine
Notary Public

My Commission Expires June 4, 1959.

PLUGGING			
FILE	SEC 13	T 29	R 12W
BOOK	PAGE 81	LINE	29