


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rice County, Sec. 5 Twp 21 Rge. 8 (E) (W)
Location as "NE/CNW&SW" or footage from lines N/2 SE SE
Lease Owner Raymond Oil Co., Inc.
Lease Name Blackhall #1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 7/27/71 19
Plugging completed 8/2/71 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation Depth to top Bottom Total Depth of Well 3586 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	203	none
				5 1/2"	3579'	2635'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, pushed plug to 3000', sanded to 2990' and set 5 sacks of cement. Rigged up on 5 1/2", shot pipe at 2848', pressured up, shot pipe at 2782', 2721', 2653', ~~xxxx~~ spotted 40 barrels oil. Pulled 83 joints of 5 1/2" casing. Set rock bridge at 203', ran 5 sacks of cement. Bailed hole dry and dumped 20 sacks of cement. Mudded hole to 30' and ran 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 4th day of August, 19 71

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

RAYMOND OIL COMPANY, INC.
#1 BLACKHALL
N/2 SE/4 SE/4 Sec. 5-21S-8W
Rice County, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1971
CONSERVATION DIVISION
Wichita, Kansas

ELEVATION: 1655 KB
1653 DF
1651 GL

Drilling Contractor: Company Tools
Date Commenced: September 29, 1966
Date Completed: October 11, 1966

Casing Record
203' 8-5/8" w/200 sx.
3579' 5-1/2" w/150 sx.

Figures Indicate Bottom of Formation


Sand & Red Bed	203
Shale & Red Bed	205
Anhydrite	219
Shale & Red Bed	505
Shale	1030
Shale & Shells	1130
Shale & Lime	1247
Lime & Shale	1500
Shale & Lime Streaks	1650
Lime w/Shale	1745
Shale w/Lime	2280
Shale & Lime	2307
Lime & Shale	2714
Shale & Lime	2845
Shale w/Lime	2865
Lime w/Shale	2945
Lime	3195
Lime & Shale	3206
Lime, Shale & Chert	3230
Chert & Lime	3272
Lime & Chert	3285
Misener Sand	3305
Lime & Shale	3324
Lime w/Shale & Sand, Chert	3355
Lime & Sand	3385
Lime, Shale & Sand Streaks	3420
Lime, Shale w/Sand Streaks	3551
Arbuckle	3556
Lime, Shale & Chert	3466
Arbuckle	3486
Dolomite & Chert	3558
Lime, Chert w/Shale	3586
RTD	3586

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I hereby certify that the above is true and correct to the best of my knowledge.


Wm. M. Raymond

Subscribed and sworn to before me, this 18th day of October, 1966.


Ronnie Donnelly - Notary Public

My commission expires: 2-15-67

