

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-159-20814-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Rice County. Sec. 5 Twp. 21S Rge. 8W E/W  
Location as "NE/CNW/SW" or footage from lines  
75' North of SW SE SE

Lease Owner Howell Oil Company  
Lease Name Blackhall #1 Well No. 1

Office Address P. O. Box 2091 Washington Center, Hutchinson KS  
Character of Well (Completed as Oil, Gas or Dry Hole) 67501

Dry Hole


Date Well completed May 13, 1979 19  
Application for plugging filed May 12, 1979 19  
Application for plugging approved May 12, 1979 19  
Plugging commenced 2:30 AM May 13, 1979 19  
Plugging completed 4:00 AM May 13, 1979 19  
Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Towman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3447'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above  
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	214'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud.  
Spot 40 sacks through open end drill pipe  
at 500'; 25 sacks at 210'; solid bridge  
at 40', 1/2 sack hulls, Howco plug and  
10 sacks in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.  
F. A. Wuellner (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
STERLING DRILLING COMPANY  
F. A. Wuellner, Secretary  
P. O. Box 129, Sterling, Kansas 67579  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of May, 19 79.



[Signature]  
Charles M. Hall, Notary Public.

My commission expires \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION

MAY 24 1979  
05-24-79  
CONSERVATION DIVISION  
Wichita, Kansas

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- BLACKHALL #1

Located: 75' north of SW SE SE, Section 5-21E-8W, Rice  
County, Kansas

OWNER: Howell Oil Company  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 7, 1979  
COMPLETED: May 13, 1979

TOTAL DEPTH: 3447'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Sand	Ran 5 joints 8 5/8", 29# used casing, 202'
90 - 218 Red Bed	cemented at 214' K.B. with 225 sacks 60/40
218 - 710 Shale, Red Bed	Pozmix #1 with 3% cc., by Halliburton.
710 - 1330 Shale	Plug down at 11:15 PM; 5-7-79.
1330 - 2965 Lime and Shale	
2965 - 3447 Lime	Plugged.

STERLING DRILLING COMPANY  
MAY 13 1979  
MISSOURI