

15-159-30312-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rice County, Sec. 5 Twp. 21 Rge. 8 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW SE SE  
Lease Owner. Raymond Oil Co., Inc.  
Lease Name. Blackhall #3 Well No.  
Office Address. Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 8/2/71 19  
Plugging completed 8/9/71 19  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman  
Producing formation Depth to top Bottom Total Depth of Well 3550 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4 7"	204 3459	none 1417'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded hole to 3400' and set 6 sacks of cement.  
Rigged up over 7", shot pipe at 2750', spotted 40 barrels of oil.  
Shot pipe at 2647', 2550', 2451', 2349', 2246', 2145', 2047', 1950',  
1860', 1784', 1693', 1653', 1545', 1442', scoped up for long pipe,  
pulled pipe. Set rock bridge at 203', to 195', set 10 sacks of cement.  
Bailed hole dry, dumped 25 sacks of cement. Mudded hole to 30' and ran  
15 sacks of cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 13 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor. KNIGHT CASING PULLING CO., INC.  
Address. CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, SS.  
NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS  
(Address)

Subscribed and sworn to before me this 10th day of August, 1971

MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

Margaret Melcher  
Notary Public.

RAYMOND OIL COMPANY, INC.  
 #3 BLACKHALL  
 Approx. SW SE SE Sec. 5-21S-8W  
 Rice County, Kansas

ELEVATION: 1655 KB  
 1653 DF  
 1650 GL

Drilling Contractor: Company Tools  
 Date Commenced: November 28, 1966  
 Date Completed: December 8, 1966

Casing Record  
 10-3/4" @ 204' w/250 sx.  
 7" @ 3459 w/175 sx.

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Sand	140
Red Bed & Shale	204
Shale & Red Bed	210
Anhydrite	219
Shale	1020
Shale & Lime	1216
Lime & Shale	1760
Shale & Lime	1950
Shale	2150
Shale & Lime	2410
Lime & Shale	2743
Shale & Lime	2847
Brown Lime	2880
Lime	2954
Lime & Shale	3019
Lime	3075
Lime & Shale	3148
Lime	3178
Conglomerate	3225
Kinderhook	3236
Lime, Chert & Sand	3267
Lime, Chert & Shale	3289
Shale, Chert & Sand	3329
Lime, Shale & Cherty Sand	3377
Lime, Chert & Sand	3409
Shale & Sand	3437
Arbuckle	3530
Lime & Chert	3550
RTD	3550

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 13 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) SS:  
 COUNTY OF SEDGWICK )

I hereby certify that the above is true and correct to the best of my knowledge.

Wm. M. Raymond  
 Wm. M. Raymond

Subscribed and sworn to before me, this 27th day of December, 1966.

Ronnie Donnelly  
 Ronnie Donnelly - Notary Public

My commission expires:  
February 15, 1967

