

15-159-20002-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Rice County, Sec. 5 Twp. 21 Rge. 8 (E) (W)

Location as "NE/CNWSW" or footage from lines 100' W of S/2 NE SE

Lease Owner Raymond Oil Co., Inc.

Lease Name Blackhall #4 Well No.

Office Address Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 10/2/72 19

Plugging completed 10/4/72 19

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Toman

Producing formation Depth to top Bottom Total Depth of Well 3532 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	203	none
				5 1/2"	3532'	2488'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, ran sand to 3450' and dumped 5 sacks of cement.
Shot pipe at 2607', pulled 40 joints. Pipe stuck, shot at 1288'
and pulled balance of pipe. Bailed fluid to 203', set 10'
rock bridge and dumped 25 sacks of cement. Mud to 40', 10'
rock bridge and dumped 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1972
10-11-72
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of October, 1972

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

My commission expires

Margaret Melcher
Notary Public.

XC: MFS
JNM

RAYMOND OIL COMPANY, INC.
 #4 BLACKHALL
 100' W-S/2-NE-SE Sec. 5-21S-8W
 Rice County, Kansas

ELEVATION: 1654 KB
 1652 DF (L&S)
 1649 GL

Drilling Contractor: Company Tools
 Date Commenced January 6, 1967
 Date Completed: January 14, 1967

Casing Record
 8-5/8" @ 203' w/250 sx.
 5-1/2" @ 3532' w/ 150 sx.

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Sand & Shale	205
Anhydrite	209
Anhydrite, Red Bed & Shale	400
Red Bed & Shale	670
Shale	1123
Lime & Shale	1865
Shale w/Lime Streaks	2120
Shale & Lime	2306
Lime	2353
Lime & Shale	2407
Topeka, Lime & Shale	2485
Lime w/Shale Streaks	2625
Lime & Shale	2706
Heebner Shale	2711
Lime & Shale	2843
Brown Lime	2875
Lime w/Shale	2960
Lime & Shale	3040
Lime	3090
Lime & Shale & Chert	3169
Lime & Shale	3179
Conglomerate Lime & Chert	3221
Kinderhook	3233
Lime, Shale, Chert & Sand	3285
Lime, Chert & Sand	3305
Lime	3388
Sand	3408
Shale, Lime & Sand	3425
Lime & Shale	3471
Lime	3532
RTD	3532

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 28 1972
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I hereby certify that the above is true and correct to the best of my knowledge.

Wm M Raymond
 Wm. M. Raymond

SUBSCRIBED and sworn to before me, this 25th day of January, 1967

Ronnie Donnelly
 Ronnie Donnelly - Notary Public

My commission expires:
 February 15, 1967

