

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec 21 Twp. 29S Rge. 17W (E) (W)

Location as "NE/CNW/SW" or footage from lines C - SW - NW  
Lease Owner J. M. HUBER CORPORATION  
Lease Name Hammond Well No. 1  
Office Address P O Box 7508 Lakeside Sta. Oklahoma City, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 8, 1963  
Application for plugging filed June 18, 1963  
Application for plugging approved Verbal, June 7, 1963  
Plugging commenced June 9, 1963  
Plugging completed June 10, 1963  
Reason for abandonment of well or producing formation Dry Hole

NORTH

X			

Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Archie Elving  
Producing formation None Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,990 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None				8-5/8"	411	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole full of mud to 240'. Cemented with 20 sacks and 1/4 sack hulls at 240'. Filled hole with mud to 40'. Cemented with 10 sacks and 1/4 sack hulls. Cemented mouse-hole and rat hole with 2 sacks each. Welded steel plate on top of surface pipe in bottom of cellar. Job completed 9:30 A.M., June 10, 1963.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 1 1963

Conservation

Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Company  
Address 617 Union Center Bldg., Wichita, Kansas

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.  
Floyd L. Meade (employee of owner) or (~~agent~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Floyd L. Meade

P O Box 7508 Lakeside Sta. Oklahoma City,  
(Address) Oklahoma.

SUBSCRIBED AND SWORN TO before me this 25th day of June, 1963

Lydial M. Woods

Notary Public.

My commission expires March 7, 1967



J. M. Huber Corporation  
 2821 N. W. 50th  
 (P. O. Box 7508, Lakeside Station)  
 Oklahoma City, Oklahoma

PRODUCTION OFFICE  
 OIL AND GAS DIVISION

TEL: AREA CODE 405  
 WINDSOR 65491

W E L L L O G

J. M. HUBER CORPORATION

Hammond No. 1

C-SW-NW, Section 21-29S-17W  
 Kiowa County, Kansas

8-5/8" Casing set @ 411'

FORMATION	From -	To
Sand-Clay	0'-	320'
Shale	320'-	411'
Red Bed-Sand	411'-	1,320'
Red Bed-Shale	1,320'-	2,200'
Shale-Shells	2,200'-	2,260'
Lime-Shale	2,260'-	2,420'
Lime	2,420'-	2,800'
Lime-Shale	2,800'-	4,638'
Lime	4,638'-	4,990'
R.T.D.	4,990'	

I hereby certify this is a true and correct well log.



Floyd L. Meade  
 District Engineer

FLM:lw

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 1 1968

CONSERVATION DIVISION  
 Wichita, Kansas