


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Kiowa County, Sec. 32 Twp. 29S Rge. 17W (E) (W)
Location as "NE/CNW/SW" or footage from lines C NE/4 NE/4
Lease Owner Davies & Fitzgerald
Lease Name Wm. Schwarm Well No. 1
Office Address 1303 Philtower Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed March 11 19 73
Application for plugging filed March 11 19 73
Application for plugging approved March 11 19 73
Plugging commenced March 11 19 73
Plugging completed March 11 19 73
Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production 19
Was cement obtained from the Conservation Division or its agents before plugging was commenced? Ralph J. Warren Yes

Name of Conservation Agent who supervised plugging of this well Ralph J. Warren
Producing formation Depth to top Bottom Total Depth of Well 4977 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	426'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cemented through 4 1/2" drill pipe to 350'
w/40 sx. Mud to 40' w/15 sx. PD @ 8:45 P.M.
by Halliburton & G.R. Biberstein

RECEIVED
STATE CORPORATION COMMISSION
MAR 15 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet.)
Name of Plugging Contractor B & B Drilling, Inc.
Address 720 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bill Lahar (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahar
720 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of March, 19 73

My commission expires 1-29-77
Butty M. Maloney Notary Public

RECEIVED
STATE CORPORATION COMMISSION
MAR 15 1973
CONSERVATION DIVISION
Wichita, Kansas

March 13, 1973

DRILLERS LOG

Re: #1 Wm. Schwarm
Cen. NE/4 NE/4
Sec. 32-29S-17W
Kiowa County, Kansas

OPERATOR: Davies & Fitzgerald
CONTRACTOR: B & B Drilling, Inc.
COMMENCED: February 26, 1973
COMPLETED: March 11, 1973

0	445	Surface Shale & Sand	8 5/8" @ 426' w/225 sx.
445	1285	Shale & Sand	
1285	1790	Shale	
1790	2300	Shale & Shells	
2300	2307	Shale	
2307	2433	Anhydrite & Shale	
2433	4211	Lime & Shale	
4211	4910	Lime	
4910	4918	Lime & Chert	DST #1 4902-4918
4918	4977	Lime & Chert	
4977		RTD	Ran log

We certify the above and foregoing to be true and correct copy of the log on the #1 Wm. Schwarm, located in Kiowa County, Kansas.

B & B DRILLING, INC.

Bill Lahar
Bill Lahar, President

Subscribed and sworn to before me this 13th day of March, 1973.

Betty M. Maloney
Betty M. Maloney Notary Public

My Commission Expires:

January 29, 1977