


15-097-00194-0000

STATE OF KANSAS  
CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

### WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section-Plot

Kiowa County, Sec. 33 Twp. 29S Rge. 17W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW/4 SE/4  
Lease Owner Skelly Oil Company  
Lease Name L. B. Jantz Well No. 1  
Office Address P. O. Box 1650, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 1-15- 1962  
Application for plugging filed 1-15- 1962  
Application for plugging approved 1-15- 1962  
Plugging commenced 1-15- 1962  
Plugging completed 1-15- 1962  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel, R.R. #2, Pretty Prairie, Ks.  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4912 Feet  
Show depth and thickness of all water, oil and gas formations.

#### OIL, GAS OR WATER RECORDS

#### CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	418'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st plug at 300' Cemented with 1/2 sack of hulls and 20 sacks of cement.  
2nd plug at 40' Cemented with 1/2 sack of hulls and 10 sacks of cement.

RECEIVED  
JAN 17 1962  
1-19-62  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet.)  
Name of Plugging Contractor Leben Drilling, Inc.  
Address P. O. Box 486, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Byron Johnson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Byron Johnson  
P. O. Box 486, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of January, 1962

My commission expires November 8, 1964  
Betty S. Edman Notary Public.

DRILLER'S LOG

COMPANY:  
CONTRACTOR:  
FARM:  
LOCATION:  
  
COMMENCED:  
COMPLETED:

Skelly Oil Company  
LEBEN DRILLING, INC.  
L. B. JANTZ #1  
SW/4 SE/4 Sec. 33-29S-17W  
KIOWA COUNTY, KANSAS  
12-31-61  
1-15-62

0	55	Rock
55	70	Blue Shale
70	535	Shale and Shells
535	945	Shale and Redbed
945	1037	Redbed
1037	1045	Anhydrite
1045	1635	Shale
1635	2045	Shale and Shells
2045	2145	Shale
2145	2245	Lime and Shale
2245	2315	Lime
2315	2515	Lime and Shale
2515	2640	Shale and Lime
2640	2950	Lime and Shale
2950	3045	Lime
3045	3180	Lime and Shale
3180	3400	Shale and Lime
3400	3540	Lime
3540	3680	Lime and Shale
3680	4859	Lime
4859	4870	Chat
4870	4892	Lime and Chat
4892	4898	Chat and Lime
4898	4912	Chert and Lime
	<u>4912</u>	<u>Rotary Total Depth - D. &amp; A.</u>

Set 8 5/8" surface casing @ 418' with 350 sacks Common & HA5 by HOWCO.

I, Byron Johnson, do hereby certify that the above and foregoing is a true and correct copy of the log of the L. B. Jantz #1, located SW/4 SE/4 of Section 33, Township 29 South, Range 17 West, Kiowa County, Kansas, as reflected by the files of Leben Drilling, Inc.

*Byron Johnson*  
Byron Johnson

RECEIVED  
STATE CORPORATION COMMISSION

JAN 19 1962

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON)

CONSERVATION DIVISION  
Public, Kansas

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 18th day of January, 1962.

*Betty S. Edman*  
Betty S. Edman, Notary Public

My Commission Expires:  
November 8, 1964