

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

KIOWA

County. Sec. 2 Twp. 29S Rge. (E) 17 (W)

Location as "NE/CNW%SW%" or footage from lines C SE SE
Lease Owner Rip C. Underwood
Lease Name Brown Well No. 1
Office Address P.O. Box 2588, Amarillo, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed: 2-7 19 64
Application for plugging filed See below 19
Application for plugging approved See below 19
Plugging commenced 2-22 19 64
Plugging completed 2-22 19 64
Reason for abandonment of well or producing formation Dry hole

NORTH

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Harold Hollis
Producing formation None Depth to top Bottom Total Depth of Well 4805 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole w/30 sacks cement set at 360'
and set 10 sacks of cement at 40'. Final
plug down at 5:30 a.m., February 22, 1964

RECEIVED
STATE CORPORATION COMMISSION

MAR 2 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton Company
Address Pratt, Kansas

STATE OF Texas, COUNTY OF Potter, ss.
H.D. Thompson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H.D. Thompson*
P.O. Box 2588, Amarillo, Texas

SUBSCRIBED AND SWORN TO before me this 28th day of February 28, 1964

My commission expires June 1, 1965

Donald W.B. Stewart
Notary Public.

Tommy Ward Drilling Company
609 Liberty Bank Building
Oklahoma City, Oklahoma

February 26, 1964

RIP C. UNDERWOOD
Brown No. 1
C SE SE, Section 2-29S-17W
Kiowa County, Kansas

Date Commenced - February 6, 1964
Date Completed - February 22, 1964
Total Depth - 4805' - D & A

Spud at 9:20 p.m. February 6, 1964
Ran 17 joints 8 5/8" (359') of surface casing
set at 359' w/250 sacks of Sunset cement.
Plug down at 10:30 a.m. February 7, 1964.

- 0 - 376' surface sand, shale and redbed
- 376 - 999' redbed and shale
- 999 - 1014' blaine anhydrite
- 1014 - 1376' red bed, sand and shale
- 1376 - 2130' shale
- 2130 - 2263' shale and lime streaks
- 2263 - 2415' lime
- 2415 - 2875' lime and shale
- 2875 - 3416' shale and lime
- 3416 - 3456' lime
- 3456 - 3559' lime and shale w/chaulk
- 3559 - 3612' lime and shale
- 3612 - 3736' lime
- 3736 - 3855' lime and shale
- 3855 - 4164' shale and lime
- 4164 - 4547' lime
- 4547 - 4615' lime and shaley lime
- 4615 - 4684' lime, shale w/chaulk streaks
- 4684 - 4735' lime, shale and chert
- 4735 - 4755' lime and chert
- 4755 - 4805' chert and shaley lime
- 4850' Total Depth
- 4805

RECEIVED
STATE CORPORATION COMMISSION
MAR 2 1964
CONSERVATION DIVISION
Wichita, Kansas

Plugged hole w/30 sacks cement set at 360' and set 10
sacks of cement at 40'. Final plug down at 5:30 a.m.
February 22, 1964.

I certify that the above Drillers Log is true and correct as taken
from the DAILY DRILLING REPORTS of the TOMMY WARD DRILLING
COMPANY.

BY Mary Limber
Mary Limber, Secretary to J. S.
Hankowsky