

15-097-10172-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kiowa

County. Sec. 6 Twp. 29S Rge. 17W (1/4) (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW

Lease Owner National Cooperative Refinery Association

Lease Name Kruse Well No. 1

Office Address 305 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 23, 1958

Application for plugging filed November 24, 1958

Application for plugging approved November 25, 1958


Plugging commenced November 23, 1958

Plugging completed November 23, 1958

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Lac Kamp

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5068 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	427'	None-Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole to 400'. Set plug with 20 sacks of cement and 1/4 sack of hulls.
Mudded hole to 35 feet, set plug with 1/4 sack of hulls and 10 sacks of cement,
filling on up to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
DEC 17 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones Drilling Company
Address 514 Orpheum Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
C. R. Sears (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears (C. R. Sears)
305 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of December, 19 58

My commission expires November 26, 1960

Nell McComb
Notary Public.

PLUGGING
FILE SEC 6 T. 29 R. 17W
BOOK PAGE 147 LINE 15

GABBERT-JONES DRILLING CO., INC.

WICHITA, KANSAS

DRILLER'S WELL LOG

KRUSE #1
 NW NW NW SECTION 6-29S-17W
 KIOWA COUNTY, KANSAS

COMMENCED 11-5-58
 COMPLETED 11-23-58

DEPTH		FORMATION	REMARKS:
FROM	To		
0	155	SURFACE SOIL & SAND	
155	200	SAND	
200	427	SHALE	RAN 427.47' OF 8 5/8" CASING CEMENTED @ 425' WITH 300 SACKS CEMENT, 2% C.C.
427	542	RED BED	
542	600	ANHYDRITE & GYP	
600	1150	SHALE, SHELLS & RED BED	
1150	1185	ANHYDRITE	
1185	2080	SHALE & SHELLS	
2080	2370	LIME & SHALE	
2370	2995	LIME	
2995	3070	LIME & SHALE	
3070	3255	SHALE	
3255	3820	SHALE & LIME	
3820	3925	LIME & CHALK	
3925	3975	LIME & SHALE	
3975	4140	LIME	
4140	4240	LIME & SHALE	
4240	4505	LIME	
4505	4537	LIME & CHERT	
4537	4906	LIME	
4906	4937	LIME, SHALE & CHERT	
4937	4960	LIME	
4960	5035	LIME & SHALE	
5035	5065	LIME	
5065	TD		DRY & ABANDONED

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 17 1958
 CONSERVATION DIVISION
 WICHITA, KANSAS

I, E. E. HALL, CERTIFY THIS TO BE A TRUE AND CORRECT COPY OF THE DRILLER'S WELL LOG FOR THE KRUSE #1.

E E Hall

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK) SS

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC, WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 24TH DAY OF NOVEMBER, 1958 PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES September 13, 1962 *Catherine Sabre*
 NOTARY PUBLIC

PLUGGING
 FILE SEC 6 T 29 R 17W
 BOOK PAGE 147 LINE 15