

15-097-00107-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Kiowa County. Sec. 6 Twp. 29S Rge. 17W (E) (W)

Location as "NE/CNW%SW%" or footage from lines C SW/4 SW/4
Lease Owner National Cooperative Refinery Association
Lease Name Fraser Well No. 1
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 9, 19 59
Application for plugging filed September 9, 19 59
Application for plugging approved September 10, 19 59
Plugging commenced September 9, 19 59
Plugging completed September 9, 19 59
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lac Kamp
Producing formation Depth to top Bottom Total Depth of Well 5065 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	416'	None-Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Mudded hole to 400'. Set wooden plug plus 1/4 sack of hulls plus 20 sacks of cement.
Mudded hole to 35', set wooden plug plus 1/4 sack of hulls plus 10 sacks of cement.
Filled on up to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
OCT 22 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address 352 North Broadway, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick
C. R. Sears (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) C. R. Sears (C. R. Sears)
305 Rule Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of October, 19 59
Nell McComb Notary Public.
My commission expires November 26, 1960

15-097-00107-0000
WELL LOG

COMPANY NATIONAL COOPERATIVE REFINING ASSOCIATION

SEC. 6 T-29S R. 17W

FARM FRASER

NO. 1

LOC. C-SW, SW


TOTAL DEPTH 5065'

COUNTY KIOWA CO., KANSAS

COMM. August 25, 1959

COMP. September 9, 1959

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 416' W/325 sax.

ELEVATION 2230' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

80	Surface clay
193	Sand
395	Blue shale
1740	Red bed
2275	Shale & shells
2545	Lime & shale
2928	Lime
3785	Shale & lime
3875	Shale & sandy lime
4019	Sandy lime & shale
4149	Lime & shale
4250	Shale & lime
4316	Lime & shale
4714	Lime
4892	Lime & shale
4904	Chert
4920	Lime & chert
4962	Chert
4971	Lime
4975	Shale
4994	Lime & chert
5033	Sand
5065	Viola
5065	T. D.

RECEIVED
STATE CORPORATION COMMISSION
OCT 22 1959
CONSTRUCTION DIVISION
Wichita, Kansas

State of KANSAS

County of BARTON

ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 FRASER well.

Verne A. Morris

Subscribed and sworn to before me this 23rd day of September 1959

My Commission Expires November 12, 1962

[Signature]
NOTARY PUBLIC