


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Ford County, Sec 25 Twp. 28 Rge. 23 (X) (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW  
Lease Owner Five Nation Drilling Co., Inc.  
Lease Name Copeland Well No. 1  
Office Address 519 Beacon Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 15 1960  
Application for plugging filed May 15 1960  
Application for plugging approved May 15 1960  
Plugging commenced May 15 1960  
Plugging completed May 15 1960  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation none Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5260 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	260	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug and 1/2 sack hulls at 240' with 25 sacks of cement through drill pipe. Fill with heavy mud to 35', plug with 1/2 sack hulls and 10 sacks of cement

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 27 1960  
CONSERVATION DIVISION  
Wichita, Kansas

3-27-1960

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_  
Address \_\_\_\_\_

STATE OF Kansas COUNTY OF Sedgwick, ss.  
H. J. Groves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. J. Groves  
519 Beacon Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of May, 1960

Carol Virginia Crest  
Notary Public.

My commission expires 9/9/62

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

**COPY**


15-057-00034-0000

Company- FIVE NATION DRILLING COMPANY, INC. SEC. 25 T. 28 R. 23W,  
Farm- Copeland No. 1 NW NW NW

Total Depth. 5260'  
Comm. 4-19-60 Comp. 5-15-60  
Shot or Treated.  
Contractor. Five Nation Drilling Co., Inc.  
issued. 8-20-60

County Ford

KANSAS



Elevation. 2486' RB

Production. Dry

CASING:

8" @ 260'

Figures Indicate Bottom of Formations.

shale	435
shale & red bed	625
anhydrite	665
shale & limestone	920
shale & red bed	1505
anhydrite	1535
shale & limestone w/red bed	1770
shale & limestone	2265
limestone	2720
limestone & shale	2765
limestone	2865
shale & limestone	2925
limestone & shale	3020
limestone	3050
limestone & shale	3240
limestone	3275
limestone & shale	3380
limestone	3505
limestone & shale	3650
limestone	3700
limestone & shale	3780
limestone	3832
shale & limestone	4055
limestone	4115
shale & limestone	4135
limestone & shale	4585
limestone	4638
limestone & shale	4718
shale	4783
limestone & shale	5160
limestone	5260
Total Depth	

TOPS:

Heobner	4297
Brown Lime	4440
Lansing	4450
Base Kansas City	4898
Conglomerate	5152
Mississippi	5166

RECEIVED  
STATE CORPORATION COMMISSION

DEC 14 1962

CONSERVATION DIVISION  
Wichita, Kansas