

15-059-00011-0060

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ford County, Sec. 22 Twp 28S Rge. (E) 25 (W)

Location as "NE/CNW/SW" or footage from lines 330' FSL & 1650' FWL

Lease Owner Kewanee Oil Company

Lease Name Burnett Well No. 1

Office Address P. O. Box 360, Hoisington, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 7, 19 56

Application for plugging filed August 7, 19 56

Application for plugging approved File 88-18 August 7, 19 56

Plugging commenced August 7, 19 56

Plugging completed August 7, 19 56

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 6280 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|---------------------|---------|------|------|--------|--------|------------|
| Heebner | Dry | 4278 | | 8-5/8" | 344' | 0 |
| Lansing-Kansas City | Dry | 4388 | | | | |
| Basal Penn. Congl. | Dry | 5170 | | | | |
| Mississippi Lime | Dry | 5186 | | | | |
| Viola | Dry | 6049 | | | | |
| Simpson | Dry | 6188 | | | | |
| Arbuckle | Dry | 6229 | 6280 | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud from 6280' to 344'
1 1/2 gals. wet hulls
Halliburton plug at 344'
20 sacks cement from 344' to 293'
Mud from 293' to 35'
1 1/2 gals. wet hulls
Halliburton plug at 35'
10 sacks cement 35' to surface.

RECEIVED
STATE CORPORATION COMMISSION
AUG 18 1956
CONSERVATION DIVISION
Wichita, Kansas
8-18-1956

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graham-Michaelis Drilling Company
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
R. S. Allison (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. S. Allison
P. O. Box 360, Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of August, 19 56

My commission expires May 26, 1958
Josephine E. Poore
Notary Public.

PLUGGING
FILE SEC. 22 T 28 R 25 W
BOOK PAGE 88 LINE 18

BURNETT #1

15-057-00011-0000

Well Record

Location: SW/4 Section 22-286-25W
Ford County, Kansas

Commenced: July 5, 1956
Completed: August 8, 1956
(rotary)

Operator: Kewanee Oil Company
648 Petroleum Building
Wichita, Kansas

Contractor: Graham-Michaelis Drilling Co.
1005 East Second Street
Wichita 1, Kansas

Casing Record: 8-5/8" @ 343.00' W/300 sacks reg. cement

LOG

| | |
|------------------------|-----------|
| Clay | 124 |
| Sand | 239 |
| Gyp. & Gravel | 333 |
| Gray Pit Gravel & Clay | 347 |
| Shale & Shells | 751 |
| Shale | 1420 |
| Red Bed, Shale & Gyp. | 1837 |
| Shale & Gyp. | 2085 |
| Shale & Anhydrite | 2710 |
| Shale & Lime | 2810 |
| Shale, Lime & Chert. | 2853 |
| Shale & Lime | 3855 |
| Lime | 3940 |
| Lime & Shale | 4317 |
| Lime | 4985 |
| Lime & Shale | 5158 |
| Lime | 5183 |
| Lime & Chert. | 5239 |
| Lime | 6280, RTD |

STATE OF KANSAS)
) ss.
COUNTY OF SEDGWICK)

The undersigned, GRAHAM-MICHAELIS DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MICHAELIS DRILLING COMPANY

By

John L. James
John L. James
Geologist.

Subscribed and sworn to before me
this 16th day of August, 1956.

Mary L. Burns

My commission expires: 11/7/57.

RECEIVED
STATE CORPORATION COMMISSION
AUG 18 1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 22 T 28 R 25W
BOOK PAGE 88 LINE 18