

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 29 TWP. 29S RGE. 13W ~~XXW~~
Location as in quarters or footage from lines:
660' FSL: 1320' FEL, NE/4

Lease Owner F. G. Holl
Lease Name Lee #3-29 Well No. 3-29
Office Address 6427 East Kellogg, Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed September 20, 1982
Application for plugging filed September 19, 1982
Plugging commenced 12:45 AM September 20, 1982
Plugging completed 2:12 AM September 20, 1982
Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durant

Producing formation _____ Depth to top _____ bottom T.D. 4795'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				10 3/4"	285'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Heavy mud plugged through open ended drill pipe, 70 sacks at 660'; 50 sacks at 270', solid bridge, 1/2 sack hulls, plug and 15 sacks at 40'; 10 sacks in rathole with joint of drill pipe, 5 sacks in water well. Used 50/50 Pozmix with 4% gel and 3% cc.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
F. A. Wuellner, Secretary
(Address)

P. O. Box 129, Sterling, Kansas 6757

SUBSCRIBED AND SWORN TO before me this 20th day of September, 1982.



[Signature]
Agnes D. Wurst, Notary Public.

My Commission expires: 4-6-85

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1982

CONSERVATION DIVISION
Wichita, Kansas

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- LEE #3-29

Located: 660' FSL; 1320' FEL, NE/4, Section 29-29S-13W,
Pratt County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 11, 1982

COMPLETED: September 20, 1982

TOTAL DEPTH: 4795'

LOG

0 - 218 Shale and Sand
218 - 620 Shale and Red Beds
620 - 1230 Shale
1230 - 4685 Lime and Shale
4685 - 4758 Sand, Shale, Lime
4758 - 4795 Lime and Shale.

CASING RECORD

Ran 7 joints 10 3/4", 32# new casing.
272.79' pipe set at 285' K.B. Cemented
with 240 sacks 60/40 Pozmix with 3% cc.
Plug down at 6:30 PM, 9-11-82, by Howco.

Plugged.

RECEIVED
STATE CONSERVATION COMMISSION
SEP 23 1982
CONSERVATION DIVISION
Wichita, Kansas

Deviation Surveys: 1° at 2235'
1 3/4° at 4523'